

## **BID PACKAGE 10-003 – OLIVE GARDEN SITE UTILITIES WORK**

---

TULALIP, WASHINGTON

### **SECTION 015200 – CONSTRUCTION AIDS**

#### **PART 1 - GENERAL**

##### **1.01 REQUIREMENTS INCLUDED**

- A. Furnish, install and maintain required Construction Aids.
- B. Remove on completion of Work.

##### **1.02 RELATED REQUIREMENTS**

- A. Drawings and general provisions of Contract, including General and Special Conditions.
- B. Section 010100 – SCOPE OF WORK

#### **PART 2 - PRODUCTS**

##### **2.01 MATERIALS – GENERAL**

- A. Materials MAY BE new or used, suitable for the intended purpose, but MUST NOT VIOLATE requirements of applicable codes and standards.

##### **2.02 CONSTRUCTION AIDS**

- A. Provide construction aids and equipment required by personnel and to facilitate execution of the Work; scaffolds, staging, ladders, stairs, ramps, runways, platforms, railings, hoists, cranes, chutes and other such facilities and equipment.
  - 1. Refer to respective sections for particular requirements for each trade.
- B. Maintain facilities and equipment in first-class condition.

##### **2.03 TEMPORARY ENCLOSURES**

- A. Provide temporary enclosures as necessary to facilitate uninterrupted work progress.
  - 1. For expedited work, temporary enclosure will be the responsibility of Contractor needing the enclosure.
  - 2. For enclosures needed as a result of delays in delivery or erection of a particular enclosure, the temporary enclosure shall be installed in a timely manner, upon request, by Contractor causing the delay.

#### **PART 3 - EXECUTION**

##### **3.01 PREPARATION**

- A. Consult with Project Engineer and the Construction Manager, review site conditions and factors which affect construction procedures and construction

## **BID PACKAGE 10-003 – OLIVE GARDEN SITE UTILITIES WORK**

---

TULALIP, WASHINGTON

aids, including adjacent properties and public facilities which may be affected by execution of the Work.

### 3.02 GENERAL

- A. Comply with applicable requirements specified in sections of Division 2 through 16.
- B. Relocate construction aids as required by progress of construction, by storage or work requirements, and to accommodate legitimate requirements of Owner and other contractors employed at the site.

### 3.03 REMOVAL

- A. Completely remove temporary materials, equipment and services:
  - 1. When construction needs can be met by use of permanent construction.
  - 2. At completion of Project or as directed by the Construction Manager.
- B. Clean, restore and repair damage caused by installation or by use of temporary installations as required.
- C. Restore existing facilities used for temporary purposes to specified, or to original condition.

**END OF SECTION 015200**