

## **BID PACKAGE 10-003 – OLIVE GARDEN SITE UTILITES WORK**

---

TULALIP, WASHINGTON

### **SECTION 015600 – CONSTRUCTION CLEANING**

#### **PART 1 – GENERAL**

##### **1.01 REQUIREMENTS INCLUDED**

- A. Execute cleaning and properly disposal of waste materials, debris and rubbish during construction.
- B. Final cleaning of project.

##### **1.02 RELATED REQUIREMENTS**

- A. Drawings and general provisions of Contract, including General and Special Conditions.
- B. Section 010100 – SCOPE OF WORK.
- C. Individual Specifications Sections: Specific cleaning for product or Work.

##### **1.03 REQUIREMENTS OF REGULATORY AGENCIES**

- A. Conduct cleaning and disposal operations to comply with codes, ordinances, regulations, and anti-pollution laws.

##### **1.04 DESCRIPTION**

- A. Maintain areas under Contractor's control free of waste materials, debris and rubbish. Maintain site in a clean and orderly condition.
- B. Contractor shall provide covered containers for deposit of debris and rubbish, including periodic disposal of accumulations of extraneous materials.
- C. NOT USED.
- D. Execute final cleaning prior to final inspection of the Work.
- E. Contractor shall perform a GENERAL TRASH CLEAN-UP of the Project on a daily basis or more frequently, as required, to maintain the Project in a clean, safe and orderly manner. However, this does not preclude Contractor or any subcontractor from cleaning up any particular debris on a more frequent basis. Contractor shall supervise and manage all Project clean-up activities.
- F. Include a line item in the Contract Cost Breakdown equal to the cost of two (2) men for one (1) full day, for each week, for the duration of the Contract. Money will be deducted from this line item on an as needed basis, if Contractor fails to perform the cleaning as stated above.

#### **PART 2 – PRODUCTS – NOT USED**

#### **PART 3 – EXECUTION**

## **BID PACKAGE 10-003 – OLIVE GARDEN SITE UTILITES WORK**

---

TULALIP, WASHINGTON

### 3.01 DURING CONSTRUCTION

- A. Contractor shall execute daily cleaning to keep the Work, the site and adjacent properties free from accumulations of waste materials, rubbish and windblown debris, resulting from contractor's construction operations.
- B. Contractor shall dispose of waste materials, cartons, crating, debris, and rubbish at designated waste receptor provided (i.e. dumpster, truck, etc.), and which shall be disposed of at a legal disposal area away from the site.
- C. NOT USED.
- D. NOT USED.
- E. NOT USED.

### 3.02 FOR WORK IN OCCUPIED AREAS – NOT USED

### 3.03 DUST CONTROL

- A. Contractor shall be required to water the site on a regular basis, as necessary to reduce dust emissions as a result of construction activities.

### 3.04 DISPOSAL

- A. Unless stated otherwise in Section 010100 – SCOPE OF WORK, Contractor will remove collected waste materials, debris, and rubbish from site weekly and dispose of off-site.

### 3.05 FINAL CLEANING

- A. Contractor shall:
  - 1. Remove waste, debris, and surplus materials from site. Clean grounds; remove stains, spills, and foreign substances from paved areas and sweep. Rake clean other exterior surfaces.

**END OF SECTION 015600**