

BID PACKAGE 10-003 – OLIVE GARDEN SITE UTILITIES WORK

TULALIP, WASHINGTON

SECTION 015800 – PROJECT IDENTIFICATION AND SIGNS

PART 1 – GENERAL

1.01 REQUIREMENTS INCLUDED

- A. Contractor shall provide and be responsible for maintaining and updating the Project identification sign throughout the duration of the Project.
- B. Contractor shall provide temporary on-site informational signs:
 - 1. As may be required by local codes, laws and regulatory agencies.
 - 2. To identify key elements of the construction facilities.
 - 3. To direct traffic.
 - 4. To facilitate trade gate system if required.
 - 5. Provide other signs as may be required such as "NO TRESPASSING", "NO PARKING", Safety Signs, and directional signs as directed by the Construction Manager.
 - 6. To identify public access areas and construction areas so as to maintain an orderly site and protect public safety.
 - 7. As they relate to occupancy and egress requirements for the existing building in conjunction with construction areas.
- C. No other signs shall be displayed.

1.02 RELATED REQUIREMENTS

- A. Drawings and general provisions of Contract, including General and Special Conditions.
- B. Section 010100 – SCOPE OF WORK.

1.03 PROJECT IDENTIFICATION SIGN – NOT USED

1.04 INFORMATIONAL SIGNS

- A. Painted signs with painted lettering or standard products.
 - 1. Size of Signs and Lettering: As required by regulatory agencies or as appropriate to usage.
 - 2. Colors: As required by regulatory agencies, otherwise of uniform colors throughout Project.
- B. Erect at appropriate locations to provide required information or as requested by the Construction Manager.

BID PACKAGE 10-003 – OLIVE GARDEN SITE UTILITIES WORK

TULALIP, WASHINGTON

1.05 QUALITY ASSURANCE

- A. Sign Painter: Professional experienced in the type of work required.
- B. Paint Finishes: Adequate to resist weathering and fading for scheduled construction period.

PART 2 – PRODUCTS

2.01 SIGN MATERIALS

- A. Structure and Framing: May be new or used, wood or metal, in sound condition structurally adequate to work and suitable for specified finish.
- B. Sign Surfaces: Exterior softwood plywood with medium density overlay, unless otherwise specified in the Contract Documents, standard large sizes to minimize joints.
 - 1. Thickness: In accordance with details.
- C. Rough Hardware: Galvanized
- D. Paint: Exterior quality.
 - 1. Use Bulletin colors for graphics.
 - 2. Colors for structure, framing, sign surfaces and graphics: In accordance with details.

PART 3 - EXECUTION

3.01 INFORMATIONAL SIGNS

- A. Paint exposed surfaces: One coat of primer and one coat of exterior paint.
- B. Paint graphics in styles, sizes and colors selected.
- C. Install at a height for optimum visibility, on ground-mounted poles or attached to temporary structural surfaces.

3.02 MAINTENANCE

- A. Maintain signs and supports in a neat, clean condition; repair damages to structure, framing or sign.
- B. Relocate informational signs as required by progress of the Work.

3.03 REMOVAL

- A. Contractor shall remove signs, framing, supports and foundations upon completion of the Project or as requested by the Construction Manager.

END OF SECTION 015800